HASSAN DIVISION.

Notification dated 26th October 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 3 P.M., on Monday the 27th November 1939 for the construction of a combined Maternity and Child Welfare Centre at Konanur, Arkalgud Taluk, Hassan District.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for the construction of a combined Maternity and Child Welfare Centre at Konanur, Arkalgud Taluk, Hassan District."

The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 550 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised, and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities in estimates are only approximate and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer, or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of March 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty up to Rs. which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will be, however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

23. Tender forms can be obtained in the Executive Engineer, Office on payment of As. 4 for each copy.

Abstract Estimate for constructing combined Maternity-Ward and Child-Welfare Centre at Konanur, Arkalgud Taluk, Hassan District.

Sl. No.	Items of work	Quantity	Per	Rate Rs. a. p.
1	Earthwork excavation for foundation	151	C.yd.	0 3 0
2	Concrete stone jelly in lime mortar for foundation	802	C.ft.	0 3 6
3	Size stone in clay for foundation	4,740	,,	0 4 0
4	Superstructure brick in clay	4,527	,,	0 3 6
5	Providing cement concrete bed of 3″ thick instead of wall plate	139	,,	0 12 0
6	Burnt brick in lime mortar	383	,,	0 4 6
7	Roofing with Madras Terrace all over the building with 3″ brick jelly concrete in surki mortar and three course of flat tiles with necessary plastering to bottom and top, etc., complete	39.44	Sqr.	35 0 0
8	Teakwood work wrought and put up with two coats of wood oiling	295	C.ft.	4 12 0
9	Providing and fixing R.C.C. ventilators over doors and windows	50	S.ft.	1 0 0
10	Do R.C.C. Chajja works to windows alround 4″ thick and $2\frac{1}{2}$ projection including plastering, etc., complete	271	,,	0 12 0
11	Brick in mortar cornice alround the building 9″ thick as per design	400	R.ft.	0 8 0
12	Brick in mortar parapet wall of $1\frac{1}{2}$′ high alround the building including plastering, etc., complete	380	,,	1 0 0
13	Plastering with chunam mortar	110.51	Sqr.	3 8 0
14	White washing two coats	110.51	,,	0 4 0
15	Cement pointing to basement	7.54	,,	3 8 0
16	Flooring with $1\frac{1}{2}$″ thick cement concrete with coloured cement plaster on 3″ lime mortar concrete bed, etc., complete	27.86	Sqr.	20 0 0
17	Providing and fixing R. S. girders including hoisting, etc., complete with bed plate	6.3	Cwt.	13 0 0
18	Constructing brick masonry pillars in cement mortar with necessary bases capitals and bond stones, etc., complete	254	C.ft.	0 10 0
19	Burnt stone slabs 6″ thick dressed and fixed	949	S.ft.	0 8 0
20	Teakwood doors 3″×4″ frames $1\frac{1}{4}$″ thick panelled shutters zinc door locks with iron fittings, etc., complete including glazed ventilators and painting complete	504	S.ft.	2 0 0
21	Teakwood panelled windows with 3″×4″ frames and $1\frac{1}{4}$″ thick shutters and parliamentary hinges with necessary ventilators including iron fittings, etc., complete with painting	547	S.ft.	2 0 0
22	Rainwater down take pipes of galvanized iron including fixing with necessary bendings, etc., complete	144	R.ft.	0 6 0
23	Water supply and sanitary fittings	L. S.	..	300 0 0
24	Boxing the girders with cement mortar, etc., complete	20	R.ft.	1 0 0

P. SUBBA RAO,
Executive Engineer.

ANJANAPUR DIVISION.

Abstract Notification dated 17th October 1939.

The attention of the public is drawn to the tender notification published in pages 2140-2141, Part VI of the *Mysore Gazette*, dated 26th October 1939, calling for tenders for "Opening out a high level feeder channel from Mallapur tank, Regd. No. 465-505 of Shikarpur Taluk."

The last date fixed for the receipt of tenders in this office is 6 P.M. on the 15th November 1939.

M. VENKATAKRISHNA RAO,
Executive Engineer.